

CESR STATUS AND RUN PLAN

D. RUBIN FOR CESR OPERATIONS GROUP

SEPTEMBER 28, 2001

- Summary of 4s run
 - Machine configuration
 - Luminosity limit
- Machine Upgrade
 - Positron converter
 - Superconducting IR quads
 - x-ray beam line
- Commissioning
- Resonance run plan




4S RUN

1430601-002

2

- Machine Configuration

- Electrostatically separated orbits
- Nine trains with 5 bunches/train in each beam
- $\pm 2.5\text{mrad}$ crossing angle
- 8mA/bunch
- Bunch spacing within each train - 14ns





INTERACTION REGION


- 1.5m REC final focus quadrupole


- Solenoid compensation by rotation of IR quads

- $\beta_v^* = 18\text{mm} \rightarrow 21\text{mm}$

- $\beta_h^* = 94\text{cm}$

- $\sigma_l = 18\text{mm}$







SUPERCONDUCTING RF

- 4- single cell - 500MHz superconducting RF cavities

T 4.5K
 $< G >$ 6.2MV/m
 \hat{V} 7.4MV
 I_{total} 750mA
 P_{beam} 1.1 MW
 P_{HOM} 2.75kW/load
 $P_{max}/cavity$ 294kW



LUMINOSITY LIMITS



- 9 trains with 4 bunches/train

- $\xi_v \sim 0.07$

- Tune shift saturates at 7.5mA/bunch

- Beam-beam limited - increased bunch current → poor lifetime and deteriorating specific luminosity

- $\xi_v \sim 0.065$


- Tune shift saturates at 7mA/bunch

- Specific luminosity decreases with increasing current

PARASITIC BEAM-BEAM INTERACTION

- Uneven spacing \Rightarrow bunch dependent tune and closed orbit
 - Closed orbit $x(s) \sim a\sqrt{\beta_h(s)} \sin(\phi_h(s) - \phi_0)$
 - Long range beam-beam tune shift
- $$\Delta Q_h \sim \frac{I_b \beta_h}{x^2} = \frac{I_b}{\sin^2(\phi_h(s) - \phi_0)}$$

Bunch dependent electron positron orbit difference at IP for first 3 trains with 7.5mA/bunch. $\sigma_y \sim 4\mu.$ \rightarrow




Bunch dependent tune shift for first 3 trains with 7.5mA/bunch. \rightarrow



PARASITIC BEAM-BEAM INTERACTION


- Horizontal tails
 - Minimum separation $\sim 7\sigma_x$
 - Tails of the bunch approach core of counterrotating bunch \rightarrow large vertical tuneshift and particle losses
- Bunch dependent luminosity
 - Bunches at center of train yield 25% higher luminosity than bunches at ends of the train




Separation at parasitic crossing points in units of horizontal rms beam size



4S PERFORMANCE



LUMINOSITY HISTORY





UPGRADE

- Superconducting IR quads
 - Energy reach
- Positron Converter
 - Increased positron production rate
- x-ray beam line


SUPERCONDUCTING IR QUADS



- Objectives
 - Extend energy reach
 - Reduce β_v^* from 18mm to < 1cm and β_v at parasitic crossing nearest IP
 - Electromagnetic vs PM quad \Rightarrow capability for precise correction of final focus optics and solenoid compensation
- Parameters
 - V and H focus quad in each cryostat
 - Gradient - 48.4T/m
 - Peak field - 6 T
 - $I \sim 1225\text{A}$
 - Length - 65cm
 - All quads rotated 4.5° (solenoid compensation)
 - Superimposed skew quadrupoles (fine tuning of solenoid compensation)
 - Superimposed dipole (orbit correction)
 - Support and remote positioning of cryostat by eccentric cam bearings

Superconducting quadrupole status


- Installed in IR - August-September
- Individual coils operated at 10% above design current in 1.5T CLEO solenoid
- Field quality
 - Skew sextupole moment in Q2 cancelled with resistive corrector located adjacent to cryostat
 - Sextupole moment in Q1 introduces tonality (differential tunes) that is corrected with chromaticity sextupoles



POSITRON CONVERTER

Non HEP time is dominated by positron top off.

- Pulsed solenoid lens
- Flux concentrator maximizes field immediately beyond target
- Peak $B_z \sim 20\text{ kG}$
- $I \sim 4\text{ kA}$
- 7.06mm tungsten-iron target
- First measurements indicate $> X2$ accelerated positron beam
- (Mitsubishi klystrons yield higher energy electron beam on target)





G-LINE

- New x-ray beam line
 - X-rays from electron beam accessible in already existing facility
 - X-rays from positron beam accessible in newly constructed facility, through new opening in tunnel wall

- Wiggler parameters

Number of poles	50
Period[cm]	12
Peak magnetic field[T]	0.8
Gap[cm]	4
Pole width[cm]	11

COMMISSIONING PLAN


- Alignment of IR quads is critical
- 0.5mm vertical displacement of Q01 → 22mm orbit error
- Startup optics
 - $\beta^* \sim 10\text{m}$
 - $k_{Q1} = -0.1$ (5% nominal)
- Procedure
 - Store beam in startup optics
 - Align quadrupoles with remote positioning system
 - Dump beam and adjust quad rails
 - Load 3s luminosity optics and repeat

Υ RESONANCE RUN PLAN

	Υ_{3S}	Υ_{1S}	Υ_{2S}	Follow up
Beam Energy[GeV]	5.175	4.7	5.	?
Luminosity [$\text{pb}^{-1}/\text{day}$]	33	23	25	?
Start date	15-Nov-01	1-Feb-02	1-May-02	25-Jun-02
Total [fb^{-1}]	1.2	1.2	0.7	?
• Machine studies	2 days/week			

MACHINE DEVELOPMENT - ψ'' (1.89GeV)

- 1.88GeV
- 20cm permanent magnet quad
- $k = -5.09m^{-2}$
- $Q1 - k = -1.92m^{-2}$
- $Q2 - k = 1.32m^{-2}$
- CLEO solenoid @ 1.0T
- All IR quads rotated 4.5° about axis
- skew quad coils superimposed on Q1 and Q2 permit compensation of coupling over wide range



MACHINE DEVELOPMENT - ROUND BEAMS


$$\xi = \frac{Nr_e}{\gamma} \frac{\beta}{4\pi\sigma^2} = \frac{Nr_e}{\gamma} \frac{1}{4\pi\epsilon} \quad (1)$$

$$\Rightarrow L = \frac{N\gamma f_c}{r_e \beta} \xi \quad (2)$$

- Emittance limited by IR aperture

- Possible parameters

- $\epsilon = 100\text{nm}$
- $\xi = 0.1$
- $\beta^* = 30\text{mm}$
- $E = 1.88\text{GeV}$



\Rightarrow

- $N = 1.64 \times 10^{11}$, ($I_b = 10.3\text{mA}$)
- $L_b = 3.3 \times 10^{31} \text{cm}^{-2}\text{s}^{-1}$
- $N_b = 7, \rightarrow L = 2.3 \times 10^{32} \text{cm}^{-2}\text{s}^{-1}$
(head on)



CESR-C RUN PLAN

- August - September 2002
 - Install full size wiggler prototype
 - Remove one pair of arc dipoles to make space for wigglers
 - Install CLEO vertex detector
- October - December 2002
 - Beam tests with wiggler
 - Explore operation at J/ψ
 - Run CESR at 5.3GeV for x-ray physics
- January-February 2003
 - Install 6 additional wigglers
 - Complete installation of cryo-distribution
- March - April 2003
 - Beam tests with wiggler
 - Explore operation at J/ψ , small energy spread
- May - June 2003
 - Install 7 remaining wigglers

- July 2003 - June 2004
 - ψ'' (3.78GeV) - 2.55 fb^{-1} :255days
 - 5.3GeV/beam for x-ray physics :110days
- July 2004 - June 2005
 - ψ'' (3.78GeV) - 0.5 fb^{-1} :50days
 - Above ψ'' (4.11GeV) - 2 fb^{-1} :205days
 - 5.3GeV/beam for x-ray physics :110days
- July 2005 - June 2006
 - Above ψ'' (4.11GeV) - 1 fb^{-1} :100days
 - J/ψ (3.1GeV) - 1 fb^{-1} :155days
 - 5.3GeV/beam for x-ray physics :110days
- June 2006 - November 2006
 - Follow up